BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38910

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/18/2019-20, Date: 16.11.2019

Improvements to roads and drains at Doddabommasandra and surrounding areas in ward no 10 (Doddabommasandra), Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N.M.Shiva kumar		
				In Figures		In Words
1	625.72	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately etc complete as per specifications and directions of engineer in charge of the work	Cum	1111.87	695719.30	Rupees One Thousand One Hundred Eleven and Eighty Seven Paise Only
2	404.59	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	388.48	157175.12	Rupees Three Hundred Eighty Eight and Forty Eight Paise Only
3	469.29	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5677.99	2664623.93	Rupees Five Thousand Six Hundred Seventy Seven and Ninety Nine Paise Only
4	391.08	Construction of un-reinforced plain cement concrete pavement, using grade concrete M30 over a prepared base with OPC course aggregate at 0.69 cum fine aggregates at 0.46 cum course and fine aggregtes confirming to IS : 383-2016, with superplastisiser @3lts confirming to IS9103-1999 mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. (with OPC 320Kg per cum GGBS 40 Kg/cum confirming to IS: 12089 course aggregate @ 0.69cum and fine aggregate @ 0.46cum) etc complete as per specifications and directions of engineer in charge of the work	Cum	5384.18	2105645.11	Rupees Five Thousand Three Hundred Eighty Four and Eighteen Paise Only

Signature of the Contractor

16/03

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/03